


ÎNVELITORI DE ACOPERIS SOLIDE



SC VIKINGPROFIL SRL

Sediul: Filipestii de Padure , str Principala, nr 19A, jud Prahova, J29/2584/2005, CUI RO18217518, tel: 0244/517080, fax: 0244/517022, email: office@vkp.ro

Fabricat la: Filipestii de Padure , str Principala, nr 19A, jud Prahova, J29/2584/2005, CUI RO18217518, tel: 0244/517080, fax: 0244/517022, email: office@vkp.ro

11

SR EN 14782:2006 (EN 14782:2006)

Placa metalica autoportanta pentru invelitori de acoperis, placari la exterior si captusiri la interior
DoP nr/...../01.04.2019

Tigla metalica tip Tigla metalica tip : KORAL RUBIN KRON ARAD

Caracteristici esentiale	Performanta declarata	Standard tehnic armonizat
REZISTENTA MECANICA	La o deschidere mai mica sau egala cu 400 mm sunt acceptate ca satisfacand aceasta cerinta fara a fi nevoie de incercari Deschidere <input type="checkbox"/> 350 Deschidere <input type="checkbox"/> 400	SR EN 14782:2006 (EN 14782:2006)
PERMEABILITATE LA APA	Impermeabila	
VARIATIE DIMENSIONALA	$24 \times 10^{-6} K^{-1}$ -pentru aluminiu	
EMISIE DE SUBSTANTE PERICULOASE	Nu elibereaza substante periculoase	
PERFORMANTA LA FOC EXTERIOR	B_{ROOF(1)} , B_{ROOF(2)} si B_{ROOF(3)}	
REACTIE LA FOC	Clasa A1	
DURABILITATE	-TABLA OTEL DX51D – grosime 0,5-0,7mm cu acoperire aliaj ALUMINIU –ZINC-SILICIU proportie 55%-43,40%-1,6%, concentratie 185g/mp - Fata 1: AluZinc 70gr - Fata 2: AluZinc 70gr	
COROZIUNE	Poate fi folosita in mediu de corozione C1 ,C2 ,C3	

Cu utilizare preconizata: invelitori de acoperis

FILIPESITII DE PADURE , PRAHOVA
DIRECTOR EXECUTIV
ION CARMEN